

**BID SCHEDULE
OREGON HILLS PARK PHASE 2
CITY OF MEDFORD**

No.	ITEM	Quantity	UNIT	UNIT COST	TOTAL
PART 00200 - TEMPORARY FEATURES AND APPURTENANCES					
00210	MOBILIZATION	ALL	LS		\$22,233
00280	EROSION & SEDIMENT CONTROL	ALL	LS		\$2,201
600					
00310	REMOVAL OF PIPES	50	LF		\$600
00320	CLEARING AND GRUBBING	0.2	ACRE		\$1,012
00330 A	GENERAL EXCAVATION	325	CUYD		\$4,875
00330 B	EMBANKMENT, IN PLACE	214	CUYD		\$2,354
00331	SUBGRADE GEOTEXTILE	770	SQYD		\$770
PART 00400 - DRAINAGE AND SEWERS					
00445 A	6 INCH STORM PIPE AND 24"x24" CATCH BASIN, COMPLETE AND IN-PLACE INCLUDING TRENCHING AND BACKFILL (SHOWN AS 4" ON C4)	40	LF		\$500
00445 B	8 INCH STORM SEWER PIPE, COMPLETE AND IN-PLACE INCLUDING TRENCHING AND BACKFILL	136	LF		\$3,400
00445C	8 INCH CLEANOUT, COMPLETE AND IN-PLACE	2	EACH		\$300
PART 00500 - BRIDGES					
00596 A	FURNISH AND INSTALL MODULAR BLOCK RETAINING WALL, COMPLETE AND IN-PLACE INCLUDING BACKFILL AND FOOTING DRAIN SYSTEM.	125	SQFT		\$3,125
00596 B	FURNISH AND INSTALL 8-INCH CONCRETE RETAINING WALL, COMPLETE AND IN-PLACE INCLUDING BACKFILL AND FOOTING DRAIN SYSTEM.	152	SQFT		\$6,080
PART 00600 - BASES					
00640 A	3/4"-0 CRUSHED ROCK BASE, COMPLETE AND IN PLACE	240	TON		\$4,320
00640 B	4"-0 CRUSHED ROCK BASE, COMPLETE AND IN PLACE	500	TON		\$8,500
PART 00700 - WEARING SURFACES					
00759 A	4 INCH - REINFORCED CONCRETE SIDEWALK	51	SQYD		\$5,610
00759 B	6 INCH - REINFORCED CONCRETE PAVEMENT	631	SQYD		\$113,580
00759 C	INSTALL ISOLATION JOINT, COMPLETE AND IN PLACE	80	LF		\$1,600
00759 D	FURNISH AND INSTALL 920-27 DECOCOLOR MP COURT SURFACE TREATMENT, OR APPROVED EQUAL, INCLUDING STRIPING, COMPLETE AND IN-PLACE	1	LS		\$5,160
00759 E	FURNISH AND INSTALL WHEELCHAIR RAMP RAILING, COMPLETE AND IN-PLACE	33	LF		\$5,000
00760	INSTALL SIDEWALK AND ADA RAMP TO CLIMBING BEAR	1	LS		\$3,000
00770	INSTALL ADA RAMP MODIFICATIONS TO EXISTING CLIMBING ROCK RAMP (REPAIRS AND IRRIGATION ARE IN PART	1	LS		\$1,500
PART 00800 - WOOD CHIP PATH					
800	FURNISH AND INSTALL NEW WOOD CHIP PATH FROM NEW ADA RAMP TO BASKETBALL COURT EAST TO EXISTING WOOD CHIP PATH. INSTALL 6" DEEP ADA RATED FALL ZONE WOOD CHIPS	1	LS		\$3,000
PART 00900 - PERMANENT TRAFFIC CONTROL AND ILLUMINATION SYSTEMS					

**BID SCHEDULE
OREGON HILLS PARK PHASE 2
CITY OF MEDFORD**

No.	ITEM	Quantity	UNIT	UNIT COST	TOTAL
00962 A	FURNISH AND INSTALL NEW AREA LIGHTS WITH LED LUMINAIRES, LITHONIA DSX1 40C LED 700 40K T4M MVOLT SPA DDBXD ON 15' SQUARE BRONZE FINISH STEEL POLES, OR APPROVED EQUAL, COMPLETE AND IN-PLACE INCLUDING FOOTINGS AND ALL APPURTENANCES.	6	EACH		\$8,000
00962 B	FURNISH AND INSTALL NEW LED LIGHTS IN SHADE STRUCTURE	ALL	LS		\$1,000
00962 C	FURNISH AND INSTALL WIRING, CONDUIT, PULL BOXES, TIMERS, AND APPURTENANCES FOR AREA LIGHTS AND SHADE STRUCTURE LIGHTS, COMPLETE AND IN-PLACE	ALL	LS		\$5,000
00962 D	FURNISH AND RETROFIT EXISTING PARKING LOT AREA LIGHTS WITH LED LUMINAIRES, LITHONIA DSX1 40C LED 700 40K T4M MVOLT SPA DDBXD, OR APPROVED EQUAL, COMPLETE AND IN-PLACE.	2	EACH		\$4,000
PART 01000 - RIGHT OF WAY DEVELOPMENT AND CONTROL					
01050 A	FURNISH AND INSTALL 4 FOOT CHAIN LINK FENCE	80	LF		\$1,600
01050 B	FURNISH AND INSTALL 5 FOOT CHAIN LINK FENCE	45	LF		\$1,125
PART 01100 - WATER SUPPLY SYSTEMS					
01170 A	FURNISH AND INSTALL MDF-MODEL10135SM DRINKING FOUNTAIN INCLUDING SUMP	1	EACH		\$4,300
01170 B	INSTALL 1 INCH PVC SCHEDULE 40 WATERLINE TO FOUNTAIN, COMPLETE AND IN PLACE	51	LF		\$765
PART 01200 - SHADE STRUCTURE					
01201	INSTALL POLIGON 20X20 SQR SHADE STRUCTURE WITH POLIGUARD RAIN GUTTER SYSTEM (SUPPLIED BY COM), COMPLETE AND IN-PLACE INCLUDING FOOTINGS AND ALL CONNECTIONS.	1	LS		\$7,000
PART 01300 - MISCELLANEOUS					
01300	FURNISH AND INSTALL BISON BA873U-BK ULTIMATE POLYCARBONATE PLAYGROUND BASKETBALL SYSTEM COMPLETE AND IN-PLACE	2	EACH		\$13,000
PART 01400 - IRRIGATION					
01400	INSTALL A COMPLETE IRRIGATION SYSTEM- LESS BID ITEM LISTED BELOW IN THIS PART 01400 - IRRIGATION	1	LS		\$30,000
01405	FURNISH, INSTALL AND MAKE FULLY FUNCTIONING A COMPLETE TORO CENTRAL CONTROL SYSTEM INCLUDING CLOCK, FLOW SENSOR, MASTER VALVE MAXI-CABLE IS EXISTING	1	LS		\$5,000
01410	PROVIDE AND INSTALL MODIFICATIONS TO IRRIGATION SYSTEM SPRINKLERS, EXTEND SLEEVES AND MAINLINE TO OUT FROM UNDER CONCRETE- AT ADA CLIMBING BEAR RAMP AND SIDEWALK. REPLACE DAMAGED LAWN WITH SOD.	1	LS		\$2,000
PART 01500 - LANDSCAPE PLANTING					
01510	INSTALL A COMPLETE LANDSCAPING SYSTEM- LESS BID ITEM LISTED BELOW IN THIS PART 01500 - LANDSCAPE PLANTING	1	LS		\$20,000
	FURNISH AND PLACE AMENDED TOPSOIL AT A MINIMUM DEPTH OF 6" IN ALL LAWN AREAS AND 4" IN PLANTED AREAS AS DIRECTED BY PROJECT MANAGER.	230	CUYD	\$12.00	\$2,760

**BID SCHEDULE
OREGON HILLS PARK PHASE 2
CITY OF MEDFORD**

No.	ITEM	Quantity	UNIT	UNIT COST	TOTAL
	ARBORIST WOOD CHIP PLACEMENT 6" DEEP- CHIPS PROVIDED BY CITY	5,600	SQFT		\$500
	LANDSCAPE WEED BARRIER FABRIC- PLACE UNDER WOOD CHIP IN AREAS DIRECTED BY PROJECT MANAGER	500	SQYD		\$500
	HYDRO-SEED 3-WAY RYE GRASS BLEND	3200	SQFT	\$0.10	\$1,000
	PLACEMENT OF (20) EXISTING ON-SITE BOULDERS	20	EACH		\$2,000
	INSTALL (1) PARK IDENTIFICATION SIGN AND (3) APPROXIMATELY 24"X18" PARK USE SIGNS. CITY TO PROVIDE SIGNS AND CONTRACTOR TO PROVIDE POLES FOR PARK USE SIGNS	1	LS		\$2,000
	PROVIDE AND INSTALL 1 - 1/2" CALIPER TREES	32	EACH	\$300.00	\$9,600
	PROVIDE AND INTSATLL 8 - 10 FT TALL PINE	8	EACH	\$300.00	\$2,400
	PROVIDE AND INTSATLL 2 GAL SHRUB	13	EACH	\$20.00	\$260
	GROUNDCOVER- PLANT 3' ON CENTER	1,750	SQFT	\$1.00	\$1,750

TOTAL BID PRICE	\$324,280
------------------------	------------------

PROPOSAL-CONTRACT OF:

Contractor _____

Address _____

By: _____

Title